



Alliance DESIGN GROUP, LLC POST ARCHITECTS, LLC

Addendum 2

RE: Date: 06.16.22
Project:
Woodworth Central Office Complex and Pineville Office/Region 3
Department of Wildlife and Fisheries
State Project No.: 16-513-14-02, F.16000160
ADG Project No.: 15025
Post Project No.: 2007

This Addendum is issued for the purpose of modifying and/or clarifying the Construction Documents and is to be construed as being as much a part of the original Construction Documents as though originally contained therein.

PRIOR APPROVAL

The following is a list of products, materials, and/or manufactures prior approved to bid the respective equipment and materials. Note that approval of a material or manufacturer does not constitute approval of a specific product. Products must meet or exceed plans and specifications in every aspect and are subject to shop drawing review.

095113 Acoustical Tile Ceilings – Certainteed, Symphony
263214 Generator - Generac

SPECIFICATIONS

General

1. This project is not sales tax exempt.

Supplemental Conditions

1. State Projects are exempt from local building permits. See section 3.7 for additional information.
2. In section 11.2, Combined Single Limit Per Occurrence, Remove "Renovations: The building value for this project is \$7,813,743.00". This renovation cost was left over from another project.

012200 – Unit Prices

1. This section is applicable to this project. Include the Unit Price Form with your Bid Form. A revised Unit Price Form and Bid Form was issued in Addendum 1.

323113 – Chainlink Fences and Gates

1. Remove paragraph C of Article 2.1. The fence will not have barbed wire.
2. Revise paragraph F of article 2.2, to 9 gage wire.
3. Revise paragraph G of article 2.2, to 7 gage wire.
4. Under paragraph A of article 2.5, 1.2 oz/sqft coating is acceptable for the framing.

DRAWINGS

SHEET C-101

1. Clarify that the removed sliding gate and associated hardware shall be returned to owner.

2. All removed trees and vegetation must be hauled off site. Burning of waste materials is not allowed.
3. Clarify that all trees in the middle of the existing gravel parking lot shall be removed. There are approximately 8) trees in this location.
4. The existing building (tagged with note DN014) and its foundations have been removed by owner. Contractor shall remove and cap any remaining utilities within the area of the new building.

SHEET A-104

1. Clarify that the roof slope on the North side of the building is 3:12.

SHEET A-601

1. Revise floor finish in 102 Meeting to CPT-1.

SHEET S-103

1. On detail 2, 3, and 9, revise the spread footing reinforcement to "#5's E.W. @ Top & Bot. – **see footing schedule for amount**"
2. On detail 3 and 9, revise bent dwls to read "#5 bent dwls – **4) per footing**".

SHEET M1.00

1. Revise duct work in Meeting 102 as shown on page 3 of this Addendum.

SHEET PS1.00

1. Clarify that the gas service and meter for the generator shall be included in the base bid.

SHEET E2.00

1. Disregard all data/telephone outlet locations indicated on this sheet. Refer to Technology sheets for official data outlet locations, conduit, and wiring.

SHEET T0.00

1. In the responsibility matrix, revise the first line under Communications Division 27 to "Category **6A** Structured Cabling System."

SHEET T4.01

1. In EIA/TIA 568-B Wiring Plan, revise all instances of "Category 6" to "Category **6A**".
2. In MDF/IDF 110 Block & Relay Rack Equipment Layout, revise all instances of the following:
 - a. "Two(2) ~~CAT5E or 6~~ data" to "Two(2) CAT **6A** data".
 - b. "One (1) ~~CAT5E or 6~~ voice" to "One(1) CAT **6A** voice".

